
# C. Brookfield

Requirements	Hard surface required for +4 vehicles.
	0 ft. offset, except 15ft. if abutting residential district.
	Prohibited between the building and the street.
Exceptions/	Plan Commission may approve reduced parking if deemed wasteful or would cause traffic congestion and
Reductions	one or more of the following apply:
	Municipal parking exists within 1,000 ft.
	On-street parking within or along boundary of the District.
	Alternative transportation is available.
	<ul> <li>Adequate parking exists on an adjacent lot or within 500 ft. with adequate supply for the use.</li> <li>Shared agreement required.</li> </ul>
	• Valet parking, double-stacked parking of 9' x 36', shared parking for uses with offsetting peak hours
Landscaping	Screening required if parking is adjacent to road, O'Malley Alley and/or residential districts.
	* 100% of road frontage, except points of access.
	* Screens shall not exceed 3 ft. in height and shall include architectural elements and plant material.





# C. Oconomowoc

Requirements	•	Encourage parking behind buildings, not between buildings and primary street frontage.
	•	Design standards required for some areas on a case-by-case basis.
Exceptions/ Reductions	•	Properties zoned Mixed Commercial (MC) are exempt from off-street parking because of available municipal parking lots.



### V. Elm Grove

### Requirements

- Dimensions shall comply with the latest available edition of "Transportation and Land Developing" (Stover/Koepke, Institute of Transportation Engineers).
- Off-street parking shall be located on same lot, adjacent lot, or at an off-site location approved by Village Plan Commission. User must rent, lease, or own parking stalls.
- Shared parking is allowed if:
  - \* Sufficient # of spaces provided to meet demand of uses;
  - An executed agreement between owners submitted that demonstrates coordinated use;
  - \* The agreement addresses the issue of parking requirements in the event that the property is sold or the nature of a business and/or use changes or expands.
  - \* The shared parking spaces shall be located within a reasonable distance from the use(s) they are intended to serve as determined by the Plan Commission.
- 20 ft., except increased to 25ft. if abutting residential district and parking serves 5 or more vehicles.
- Curbs and gutters shall be at least 4 ft. from lot line to prevent vehicles from extending over lot lines.
- Lighting directed onto parking area only.

# Exceptions/ Reductions

• Plan Commission may approve reduced parking if deemed unnecessary. If a change in use occurs, new use must comply with parking standards.





# V. Pewaukee

# Requirements

- Business development is subject to 80% of ordinance standards for # of spaces required.
- Street parking qualifies subject to plan commission approval of location and design.
- 3 ft. parking offset unless shared with adjacent property. Shared parking is encouraged.
- No parking is allowed between road and building unless approved by Plan Commission as part of public parking plan.
- If parking is proposed on an adjacent lot, access, parking and maintenance easements/agreements are required
- Parking shall be arranged and marked to provide orderly and safe parking and storage of vehicles.
- Space must be set aside for reduced parking in order to convert space to parking in the future.

# Exceptions/ Reductions

• The Plan Commission may allow deviations from the parking requirements.

# Landscaping

• If buildings are set back, dense landscaping or decorate fencing should be used to help define the street edge.





### V. Hartland

# Requirements No parking between front of building and street, unless Plan Commission determines that the requirement is infeasible for the site. Encourages shared access drives and interconnecting traffic aisles. Parking for 5 or more vehicles should have aisles and parking spaces clearly marked . Parking spaces perpendicular to roads and with direct access without a service drive are prohibited. Curbs/barriers min. of 4 ft., from a property line to prevent vehicles from extending over the lot line and 3 ft. from structures, fences, walls, and plants. Adequate space should be provided for landscaping and visual screening to help prevent vehicles from backing into sidewalks and streets. Lighting shall provide safe movement of traffic, promote security/crime prevention, create aesthetically pleasing environment at night and day. Screening between a lot and residential district shall be a min. of 6 ft. in height and 10 ft. between loading area and residential at time of installation, unless waived by the Plan Commission. **Exceptions/** Adjustments to the # of parking may be warranted to avoid constructing unneeded and excessive impervious surfaces that could otherwise be landscaped open space. Reductions Payment in-lieu of providing off-street parking in B-3. Landscaping Landscaping near parking lots and streets should be salt-tolerant. There are detailed drawings in VCRP for street landscaping and property screening landscaping. All public and private off-street parking areas which serve five or more vehicles shall provide landscaping in compliance with strict village standards. Terrace/street trees shall be planted to provide a street frontage buffer where required. Trees and shrubs shall not create blind spots along traffic ways for pedestrians or vehicular traffic. Parking and loading/unloading areas shall be screened from the road by a wall, fence, berm, or plants as deemed appropriate by the Plan Commission. Screening shall be at least 3 ft. in height as measured within 3 years, with min. height of 18 in. at time of installation. A landscape bed of at least 150 sq. ft. should be placed at the base of freestanding advertisement signs.










### C. Waukesha

# Requirements/ exceptions

- Minimum parking space size: 9' x 18'.
- Downtown parking district is exempt from off street loading requirements, parking requirements, and number of spots as listed in the code.
- Residential parking requires Plan Commission review.









# V. Mt. Horeb

## Requirements

• No parking required and no parking allowed along the street edge unless required as part of a CU or Planned Development.

# C. Cedarburg

# Parking must take place on same lot as the principal use or not over 400 ft. from use. Adjustments can be made with Plan Commission approval in order to avoid unneeded and excessive parking facilities. Reductions Adjustments can be made with Plan Commission approval in order to avoid unneeded and excessive parking facilities. Reducing the area can reduce impervious surfaces, minimize stormwater runoff, avoid excessive stormwater management facilities, provide more landscape area and open space. \* Must demonstrate parking demands do not meet requirements, availability of shared parking, use of on-street parking (within 250 ft. of entrance), use of alternative transportation. \* Space must be set aside to accommodate additional parking otherwise required. If the use changes or becomes more intense, additional parking may be required.